

14mt Pod cat

LOA 14 mts
Beam 8 mts
Disp 4600 kgs [max gross]
SA 90 sq mts [working]
construction time [un painted shell]
1100 hrs
finished 2950 hrs [simple fitout]
To be kept as simple as possible.
1 x 25/50 4stroke outboard
2 x 21 hp diesel
Wheel or Tiller steering.
Pod has 1 x queen 2 x double.
A toilet and shower enclosure, Galley and nav area.
Under \$150k plus labour.

© Bob Oram design
0741258458

